

# SUN WEST ENGINEERING SPEC SHEET

Sun West Product - COP (Cell-on-Platform)

Description	Specification	Additional Info.
<b>Frame</b>		
Frame Material	.187" Hot Rolled Steel 10" formed frame and supprt assembly	Fully Hot Dipped Galvanized
Frame Width	96"	
Frame Length	259"	
Leveling Jacks	4	5,000# Max
Outriggers	4	Multi Position
Storage Boxes Standard Size	62"W X 16"H X 24"D	Linex Coated Interior/Locking
Hardware	Grade 8/Yellow Zinc	Stainless Steel as required
Jack Pads	16 X 16 X 1	4
Utility Tool Box	As Required	Linex Coated Interior/Locking

<b>Crows Nest</b>	2" X 2" X .187 Wall Tube	Galvanized
-------------------	--------------------------	------------

<b>Mast</b>		
Mast	10.3-60	450# Lift/Pay Load
Compressor	TA-6052	120 Volt
Controls	Pneumatic Valve Type	
Trip J Hook	1	
Guy Kit	Augers/Cables/Hardware	1

Equipment Cabinet	Equipment Cabinet
17'-3"L X 8' W X 9'-3" H	Smoke Alarm N/C Dry Contacts
U.L. Listed NEMA 3R Alumimum Cabinet	Interior Lighting With Emergency Ballasts
Standing Rib Roof Design	Manual Transfer Switch
Heavy Duty Door Hardware	Appleton Receptacle
Finish: White Polyester Powder Coat	Surge Suppression-Utility & Generator
2-60,000 BTU/hr HVAC units	RF (COAX) Entry as Required per configuration
Lead / Lag Controller	Exterior GFI Receptacle
High & Low Alarm N/C Dry Contacts	200 Amp 120.240 1Ø, 42 Position Distribution Panel
Intrusion Alarm N/C Dry Contacts	
Ceiling Mounted Ladder Rack Over Equipment	
Equipment Rack Mounting Provisions	
R-4 Reflective Ffoil Insulation	
Main Ground Bar	
Equipment Ground Bar	
Halo Grounding	
Fire Extinguisher	
First Aid Kit	
Eye Wash Kit	