

SUN WEST ENGINEERING SPEC SHEET

Sun West Product - Flex-Line Equipment Cabinet

DESCRIPTION	SPECIFICATION
Cabinet Dimensions	TBD By Customer Configuration
Cabinet Weight	TBD By Configuration (Less Customer Equipment)
Cabinet Material	Aluminum, Welded Construction
6" Base Frame	Steel, Formed, Welded, Galvanized, Fork Tubes and Crane Picks
Rating	U.L. Listed NEMA 3R Aluminum Cabinet / PE Stamped @ 150 mph Wind Load & Rated Seismic Zone 4

Features Listing
HVAC units TBD By Configuration
White Polyester Powder Coat "or" as requested
Standing Rib Roof Design
R-4 Reflective Foil Insulation
Alumimum Hinges with Stainless Steel Pins
Extra Heavy Duty Door Hardware
Ceiling Mounted Ladder Rack, As Required Per Configuration
Universal Equipment Rack Mounting Provisions
Exterior Ground Bar
Internal Equipment Ground Bar
Standard Grounding
Interior Lighting as Required Per Configuration
Electrical
Manual or Auto Transfer Switch w/ 200 Amp 120.240 1Ø, 42 Position Distribution Panel
225 AMP MB, 1PH/3W, 42-CIR, Electrical Panel
AC Power, Branch Breakers Included
Interior Service Receptacles As Required Per Configuration
Exterior GFI Receptacle
HVAC Surge Suppression
Lead / Lag Controller
High & Low Alarm With N/C Dry Contacts
Surge Suppression-Utility & Generator and Alarm With N/C Contacts
Smoke Alarm with N/C Dry Contacts
Intrusion Alarm With N/C Dry Contacts
Power Fail Alarm
16 Port R/F Entry
Passive Hydrogen Venting
Equipment Rack Mounting Provisions
Provision for Trapeze
Gen-Set Inlet or Lug Box
3/4" Thick Plywood Fire Retardant Treated