SUN WEST ENGINEERING SPEC SHEET

Sun West Product: In-Line Equipment Cabinet

DESCRIPTION	SPECIFICATION
Cabinet Dimensions	100"H x 42"W x L As required per configuration
Cabinet Weight	TBD By Configuration (Less Customer Equipment)
Cabinet Material	Aluminum, Welded Construction
Base Frame	Steel, Formed, Welded, Galvanized, Fork Tubes and Crane Picks
Rating	UL® Listed NEMA 4/3R Alumimum Cabinet

Features Listing
Alumimum Hinges with Stainless Steel Pins
3-Point Heavy Duty Door Hardware
White Polyester Powder Coat "or" as requested
HVAC units TBD By Configuration
Lead / Lag Controller
High & Low Alarm With N/C Dry Contacts
Surge Suppression-Utility & Generator and Alarm With N/C Contacts
Smoke Alarm with N/C Dry Contacts
Intrusion Alarm With N/C Dry Contacts
Ceiling Mounted Ladder Rack, As Required Per Configuration
Universal Equipment Rack Mounting Provisions
R-4 Reflective Foil Insulation
Exterior Ground Bar
Internal Equipment Ground Bar
Standard Grounding
Interior Lighting as Required Per Configuration
ILC Manual Transfer Switch w/ 200 Amp 120.240 1Ø, 42 Position Distribution Panel
Interior Service Receptacles As Required Per Configuration
16 Port R/F Entry